					DEPARTMENT	T OF NATU	IRAL RESO			AMENDE	FOR D REPORT				
	CATION OF WELL								1. WELL NAME an	nd NUMBER LC Tribal 4h	H-35-46				
2. TYPE C	OF WORK								2 FIFI D 2D WILL		1-33-40				
		DRILL NEW WE	ELL 📵 REE	ENTER P&/	A WELL DEEPEN	WELL 🔵			3. FIELD OR WILE	ALTAMO	NT				
4. TYPE C	OF WELL		Oil Well	Coalbe	d Methane Well: NO				5. UNIT or COMM	UNITIZATION A	GREEME	NT NAMI	E		
6. NAME	OF OPERATO	R	В	ILL BARRE	TT CORP				7. OPERATOR PH	ONE 303 312-	8164				
8. ADDRE	SS OF OPERA		099 18th Stree	et Ste 230	0, Denver, CO, 80202				9. OPERATOR E-	MAIL Hilgers@billbar	rettcorp.co	om			
							07475	\ _eee	12. SURFACE OW	-	07475		- (2)		
		2OG0005500	12 = 'fee')		FEDERAL IND	DIAN (III)	STATE	/ FEE	14. SURFACE OW	INDIAN ()	STATE (E (III)		
		<u> </u>	Bill	Barrett Co	orporation					303-293-	9100				
15. ADDR	RESS OF SURF			16. SURFACE OV	VNER E-MAIL (i	f box 12 =	: 'fee')								
		OR TRIBE NAME					ODUCTION	FROM	19. SLANT						
(II DOX II	z = INDIAN)				YES (Submit C	Commingling	g Application	n) NO 📵	VERTICAL 🗍	DIRECTIONAL	🔵 но	RIZONTA	AL 📵		
20. LOC	LOCATION OF WELL			FO	OTAGES	QTR-	QTR	SECTION	TOWNSHIP	RAN	GE	МЕ	RIDIAN		
LOCATION	ON AT SURFA	CE		552 FNI	L 1265 FEL	NEN	NE	35	4.0 S	6.0	W		U		
Top of l	Jppermost Pro	oducing Zone		660 FNI	L 1745 FEL	NWI	NE	35	4.0 S	6.0	W	U			
At Total Depth 700 F					L 700 FWL	NWN	٧W	3.5	4.0 S	W		U			
21. COUI	NTY	UINTAH			22. DISTANCE TO NEA		SE LINE (Fe	N	23. NUMBER OF	ACRES IN DRILL 640	ING UNIT				
						or Complet		200	26. PROPOSED D	6. PROPOSED DEPTH MD: 9060 TVD: 5902					
27. ELEV	ATION - GROU				28. BOND NUMBER	1 DM0074	725		29. SOURCE OF D		BER IF AP	PLICABL	E		
		7217			Hole Casing			mation		40 10					
String	Hole Size	Casing Size	Length	Weight		_			Cement		Sacks	Yield	Weight		
Cond	26	16	0 - 80		Unknown		8.8		No Used		0	0.0	0.0		
Surf	12.25	9.625	0 - 2000	36.0	J-55 ST&C	-	8.8	Halliburto	n Light , Type L	Jnknown	280	3.16	11.0		
								Halliburton	Premium , Type	Unknown	210	1.36	14.8		
I1	8.75	7	0 - 6257	26.0	P-110 LT&C	9	9.2		Unknown		280	3.14	14.8		
									Unknown		130	1.42	13.5		
L1	6.125	4.5	0 - 9060	11.6	P-110 LT&C	,	9.5		No Used		0	0.0	0.0		
					А	TTACHMI	ENTS								
	VE	RIFY THE FOL	LOWING ARI	E ATTAC	CHED IN ACCORDAN	ICE WITH	THE UTA	I OIL AND GAS	CONSERVATIO	N GENERAL	RULES				
⊮ v	VELL PLAT OR	MAP PREPARED I	BY LICENSED S	SURVEYOR	R OR ENGINEER	[COMP	LETE DRILLING P	LAN						
AI	FFIDAVIT OF S	TATUS OF SURFA	CE OWNER AG	REEMEN	T (IF FEE SURFACE)		FORM 5	5. IF OPERATOR I	S OTHER THAN TH	IE LEASE OWNE	ĒR				
I ✓ DI	RECTIONAL S	URVEY PLAN (IF	DIRECTIONAL	LY OR HO	RIZONTALLY DRILLED) [г торос	RAPHICAL MAP							
NAME V	enessa Langm	acher		TITLE S	Senior Permit Analyst			PHONE 303 3	12-8172						
SIGNATI	URE			DATE 0	05/29/2012			EMAIL vlangm	acher@billbarrettc	orp.com					
API NUM	IBER ASSIGNE	ED 4304752769000													

DRILLING PLAN

BILL BARRETT CORPORATION

LC Tribal 4H-35-46

SHL: NE NE, 552' FNL and 1265' FEL, Section 35, T4S-R6W BHL: NW NW, 700' FNL and 700' FWL, Section 35, T4S-R6W Duchesne Co., UT

Bill Barrett Corporation (BBC) intends to drill a horizontal through the prospective zone within the Uteland Butte.

1 - 3. <u>Estimated Tops of Geological Markers and Formations Expected to Contain Water, Oil and Gas and Other Minerals</u>

HORIZONTAL LEG FORMATION TOPS

HOMEONTHE LEGITORIMITION TOTS										
Formation	Depth – MD	Depth - TVD								
Green River	2,112'	2,112'								
Surface casing	2,000'	2,000'								
Mahogany	2,767'	2,767								
TGR3	3,842'	3,842								
Douglas Creek	4,627'	4,627'								
3 PT Marker	4,987	4,987'								
Black Shale Facies	5,357	5,357'								
Castle Peak	5,597	5,596'								
*Uteland Butte	6,010'	5,915'								
CR1A Base	6,211'	5,971'								
TD	9,060'	5,902'								

*PROSPECTIVE PAY

The Uteland Butte CR1 is the primary objective for oil/gas.

Base of Useable Water = 2,732'

4. <u>Casing Program</u>

Hole	SETTING DEPTH		Casing	Casing	Casing		
<u>Size</u>	<u>(FROM)</u> <u>(TO)</u>		<u>Size</u>	Weight	<u>Grade</u>	<u>Thread</u>	Condition
12-1/4"	surface	2,000'	9 5/8"	36.0 ppf	J or K 55	ST&C	New
8 3/4"	surface	6,257'	7"	26.0 ppf	P-110	LT&C	New
6 1/8"	surface	9,060'	4 1/2"	11.6 ppf	P-110	LT&C	New
			Liner with				
			4-1/2"				
			Tieback				
			for frac				

5. <u>Cementing Program</u>

9 5/8" Surface Casing	Lead with approximately 280 sx Halliburton Light Premium cement with additives mixed at 11.0 ppg (yield = 3.16 ft ³ /sx). TOC @ Surface Tail with 210 sx Premium 14.8 ppg (yield = 1.36 ft ³ /sx) calculated hole volume with 75% excess. TOC @ 1,500' Top out cement, if required: 100 sx of Premium cement with additives mixed at 15.8 ppg (yield = 1.17 ft ³ /sk)
7" Intermediate Casing	Lead with approximately 280 sx Tune Light cement with additives, mixed at 11.0 ppg (yield = $3.14 \text{ ft}^3/\text{sx}$). TOC @ 1,500' Tail with approximately 130 sx Halliburton Econocem cement with additives mixed at 13.5 ppg (yield = $1.42 \text{ ft}^3/\text{sx}$). TOC @ 4,494'
4 ½" Liner with 4-1/2" Tieback to surface	The liner will either be cemented with 300 sx 13.5 pg Econocem from TD to the TOL or uncemented with 14-16 open hole packers
Note: Top of Toil coment for the in	starmadiate string will be calculated to 1100 above the KOD

Note: Top of Tail cement for the intermediate string will be calculated to 1000 above the KOP using gauge hole plus 50% excess. Lead to 200' inside of surface caping.

6. Mud Program

<u>Interval</u>	Weight	<u>Viscos tv</u>	Fluid Loss (API filtrate)	<u>Remarks</u>
40' - 2,000'	8.4 – 8.8	36	NC	Freshwater Spud Mud Fluid System
2,000' - 6,257'	8.9 - 9.2	26 - 36	NC	Fresh Water with sweeps
6,257' – TD	9.0 - 9.5	45 – 58	4 – 10	Fresh Water PHPA

Note: Sufficient mud materials to maintain mud properties, control lost circulation and to contain "knows" with be available at wellsite. BBC may require minor amounts of diesel to be added to its flaid system in order to reduce torque and drag.

7. BOP and Pressure Containment Data

Depth Intervals BOP Equipment									
0-2,000	No pressure control required								
2,000' – TD 11" 5000# Ram Type BOP									
11" 5000# Annular BOP									
- Drilling spool to a	accommodate choke and kill lines;								
- Ancillary and cho	ke manifold to be rated @ 5000 psi;								
- Ancillary equipme	- Ancillary equipment and choke manifold rated at 5,000#. All BOP and BOPE tests will be in								
accordance with t	he requirements of onshore Order No. 2:								

- The BLM and the State of Utah Division of Oil, Gas and Mining will be notified 24 hours in advance of all BOP pressure tests.
- BOP hand wheels may be underneath the sub-structure of the rig if the drilling rig used is set up to operate most efficiently in this manner.

8. **Auxiliary Equipment**

- a) Upper kelly cock; lower Kelly cock will be installed while drilling
- b) Inside BOP or stab-in valve (available on rig floor)
- c) Safety valve(s) and subs to fit all string connections in use
- d) Mud monitoring will be visually observed

9. **Testing, Logging and Core Programs**

Cores	None anticipated;							
Testing	None anticipated; drill stem tests may be run on shows of interest;							
Sampling	30' to 50' samples; surface casing to TD. Preserve samples all show intervals;							
Surveys	MWD with GR as needed to land wellbore;							
WL Logging	None in intermediate							
Note: FMI an	Note: FMI and CAL may be run on the lateral portion of the horizontal wellbore at the pologist's							
discretion								

10.

No abnormal Pressures or Temperatures

No abnormal pressures or temperatures or other hazards are an icitated.

Maximum anticipated bottom hole pressure equals anticipated surface pressure equals pressure of a second pr oximately 2915 psi* and maximum anticipated surface pressure equals approximately 10.77 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

*Max Mud Wt x 0.052 x TD A (bottom hole pressure)

11. pe of Water Supply


Vater for the drilling and completion will be trucked from the Duchesne City Culinary Water Dock located in Sec. 1, T4S, R5W.


12. **Drilling Schedule**


November 2013 **Location Construction:** Spud: November 2013 Duration: 25 days drilling time


25 days completion time

^{**}Maximum surface pressure A - (0.22 x TD)











Bill Barrett Corp.
Project: Duchesne Co., UT (NAD27)
Site: Sec.35-T4S-R6W
Well: LC Tribal 4H-35-46
Wellbore: Wellbore #1
Design: Design #1
Lat: 40° 5' 43.598 N
Long: 110° 31' 29.460 W
Pad GL: 7217.00
KB: WELL @ 7232.00usft





Northing 643297.662

TVD

5902.00

+N/-S


0.00

LCT 4H-35-46 PBHL

Name

±F/₌W

0.00



Shape

Point

Longitude 110° 31' 29.460 W

32' 11.681 W

CASING DETAILS

SHL 1000 552' FNL, 1265' FEL SEC.35-T4S-R6W 4S-R6W SECTION LINE 660' Setback TD at 9060.32 South(-)/North(+) (100 KOP / Start Build 12.00° -500-Start 2432.81 hold at 6627.50 MD -1000 -1500 -2000 -3500 -3000 -2500 -2000 -1500 -500 1000 -4000 500 West(-)/East(+) (1000 usft/in)

True Vertical Depth (400 usft/in) No casing data is available 5600 FORMATION TOP DETAILS TVDPath **MDPath** Formation 2112.00 2112.00 Green River Mahogany Tgr3 Mkr 2767.00 3842.00 3842.00 EOC / Start DLS 3.00° TFO 89.86 5800 Douglas Creek 3PT Mkr. Black Shale 4627.00 4627.00 4987.00 4987.00 5357.00 5357.00 5596.73 5597.52 Castle Peak 6010.32 5915.77 **Uteland Butte** 6128.42 5958.06 CR1 5971.03 6211.98 CR1A Base

WELL DETAILS: LC Tribal 4H-35-46

WELLBORE TARGET DETAILS (LAT/LONG)

Ground Level:

+E/-W

-3280.98

Easting 2272797.197

+N/-S

-122.90


7217.00

Latittude


Latitude

40° 5' 42.382

40° 5' 43.598 N



Created By: Brace Verte: May Ap 95 20012





Planning Report



EDM 5000.1 Single User Db Database:

Company: Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27) Sec.35-T4S-R6W Site:

Well: LC Tribal 4H-35-46 Wellbore: Wellbore #1 Design #1 Design:

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well LC Tribal 4H-35-46 WELL @ 7232.00usft WELL @ 7232.00usft

True

Minimum Curvature

Project Duchesne Co., UT (NAD27)

US State Plane 1927 (Exact solution) Map System:

NAD 1927 (NADCON CONUS) Geo Datum:

Utah Central 4302 Map Zone:

System Datum:

Mean Sea Level

Sec.35-T4S-R6W Site

Northing: 643,297.666 usft Site Position: Latitude: 40° 5' 43.598 N From: Lat/Long Easting: 2,272,797.197 usft Longitude: 110° 31' 29.460 W **Position Uncertainty:** 0.00 usft Slot Radius: 13-3/16" **Grid Convergence:** 0.62 °

Well LC Tribal 4H-35-46

Well Position +N/-S 0.00 usft Northing: 643,297.662 usft Latitude: +E/-W

0.00 usft Easting: 2,272,797.197 usft Longitude

40° 5' 43.598 N 110° 31' 29.460 W

Position Uncertainty 0.00 usft Wellhead Elevation: usft 7,217.00 usft

Wellbore Wellbore #1 Magnetics **Model Name** Sample Date Declination Dip Angle Field Strength (nT) IGRF2010 04/25/12 65.72 52.133

Design #1 Design

Audit Notes:

Version: PLAN Tie On Depth: 0.00

Vertical Section: +N/-S +E/-W Direction

(usft) (usft) (°) 0.00 0.00 267.85

Plan Sections Measured			Vertical			Dogleg	Build	Turn		
Depth (usft)	Inclination (°)	Azimuth (°)	Depth (usft)	+N/-S (usft)	+E/-W (usft)	Rate (°/100usft)	Rate (°/100usft)	Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
5,494.68	0.00	0.00	5,494.68	0.00	0.00	0.00	0.00	0.00	0.00	
6,256.60	91.43	259.00	5,972.00	-93.38	-480.39	12.00	12.00	0.00	259.00	
6,627.50	91.43	270.13	5,962.71	-128.44	-848.93	3.00	0.00	3.00	89.86	LCT 4H-35-46 PBHL
9,060.32	91.43	270.13	5,902.00	-122.90	-3,280.98	0.00	0.00	0.00	0.00	LCT 4H-35-46 PBHL



Planning Report



EDM 5000.1 Single User Db Database: Company:

Bill Barrett Corp.

Project: Duchesne Co., UT (NAD27) Sec.35-T4S-R6W Site: Well: LC Tribal 4H-35-46 Wellbore: Wellbore #1 Design: Design #1

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well LC Tribal 4H-35-46 WELL @ 7232.00usft WELL @ 7232.00usft

True Minimum Curvature

anned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00			300.00				0.00		
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00		0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00		0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
Green River									
2,112.00	0.00	0.06	2,112,00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	6.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.0	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
Mahogany									
2,767.00	0.00	0.00	2,767.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
Tgr3 Mkr			0.010.00						
3,842.00	0.00	0.00	3,842.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00 4 400.00	0.00	በ በበ	4 400 nn	(1 (1(1					
4,400.00 4,400.00 4,500.00	0.00 0.00	0.00 0.00	4,400.00 4,500.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00



Planning Report



Database: EDM 5000.1 Single User Db

Company: Bill Barrett Corp.

 Project:
 Duchesne Co., UT (NAD27)

 Site:
 Sec.35-T4S-R6W

 Well:
 LC Tribal 4H-35-46

 Wellbore:
 Wellbore #1

 Design:
 Design #1

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well LC Tribal 4H-35-46 WELL @ 7232.00usft WELL @ 7232.00usft

True Minimum Curvature

ned Survey									
Measured			Vertical			Vertical	Dogleg	Build	Turn
Depth (usft)	Inclination (°)	Azimuth (°)	Depth (usft)	+N/-S (usft)	+E/-W (usft)	Section (usft)	Rate (°/100usft)	Rate (°/100usft)	Rate (°/100usft)
Douglas Cro		()		()	(,				
4,627.00	0.00	0.00	4,627.00	0.00	0.00	0.00	0.00	0.00	0.00
4,700.00	0.00	0.00	4,700.00	0.00	0.00	0.00	0.00	0.00	0.00
4,800.00	0.00	0.00	4,800.00	0.00	0.00	0.00	0.00	0.00	0.00
4,900.00 3PT Mkr.	0.00	0.00	4,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,987.00	0.00	0.00	4,987.00	0.00	0.00	0.00	0.00	200	0.00
5,000.00	0.00	0.00	5,000.00	0.00	0.00	0.00	0.00	-	0.00
5,100.00	0.00	0.00	5,100.00	0.00	0.00	0.00	0.00	000	0.00
5,200.00	0.00	0.00	5,200.00	0.00	0.00	0.00	0.00	0.00	0.00
5,300.00	0.00	0.00	5,300.00	0.00	0.00	0.00	0.00	0.00	0.00
Black Shale		0.00	- 0 00	2.22	0.00	0.00		0.00	0.00
5,357.00	0.00	0.00	5,357.00	0.00	0.00	0.00	0.00	0.00	0.00
5,400.00	0.00	0.00	5,400.00	0.00	0.00	0.00	0.00	0.00	0.00
	Build 12.00°	0.00	E 404 00	0.00			0.00	0.00	0.00
5,494.68 5,500.00	0.00 0.64	0.00 259.00	5,494.68 5,500.00	0.00 -0. 0 1		0.03	0.00 12.00	0.00 12.00	0.00 0.00
5,525.00	3.64	259.00	5,524.98	-0.18	-0.94	0.95	12.00	12.00	0.00
5,550.00	6.64	259.00	5,549.88	-0.61	-3.14	3.16	12.00	12.00	0.00
5,575.00	9.64	259.00	5,574.62	-1.29	-6.62	6.66	12.00	12.00	0.00
Castle Peak	(
5,597.52	12.34	259.00	5 596.73	-2.10	-10.83	10.90	12.00	12.00	0.00
5,600.00	12.64	259.00	5,599,15 5,623.39	-2.21	-11.36	11.43	12.00	12.00	0.00
5,625.00 5,650.00	15.64 18.64	259.00 259.00	5,623.39	-3.37 -4.78	-17.35 -24.58	17.46 24.74	12.00 12.00	12.00 12.00	0.00 0.00
	A 4	259.00	5,670.74		-33.03	33.24	12.00	12.00	0.00
5,675.00 5,700.00	21 64	259.00	5,693.73	-6.42 -8.29	-33.03 -42.67	33.2 4 42.95	12.00	12.00	0.00
5,725.00	27.64	259.00	5,716.17	-10.40	-53.48	53.83	12.00	12.00	0.00
5,750.00	30.64	259.00	5,738.01	-12.72	-65.43	65.86	12.00	12.00	0.00
5,775.00	33.64	259.00	5,759.17	-15.26	-78.48	79.00	12.00	12.00	0.00
5,800.00	36.64	259.00	5,779.61	-18.00	-92.60	93.21	12.00	12.00	0.00
5,825.00 5,850.00	39.64 42.64	259.00 259.00	5,799.27 5,818.10	-20.95 -24.08	-107.76 -123.90	108.47 124.71	12.00 12.00	12.00 12.00	0.00 0.00
5,875.00	45.64	259.00	5,836.04	-27.41	-140.99	141.91	12.00	12.00	0.00
5,900.00	48.64	259.00	5,853.04	-30.90	-158.97	160.02	12.00	12.00	0.00
5,925.00	51.64	259.00	5,869.07	-34.56	-177.81	178.98	12.00	12.00	0.00
5,950.00	54.64	259.00	5,884.06	-38.38	-197.44	198.74	12.00	12.00	0.00
5,975.00	57.64	259.00	5,897.99	-42.34	-217.82	219.25	12.00	12.00	0.00
6,000.00	60.64	259.00	5,910.81	-46.43	-238.88	240.45	12.00	12.00	0.00
Uteland But 6,010.32	nte 61.88	259.00	5,915.77	-48.16	-247.76	249.39	12.00	12.00	0.00
6,025.00	63.64	259.00	5,922.50	-50.65	-260.57	262.29	12.00	12.00	0.00
6,050.00	66.64	259.00 259.00	5,933.00	-50.65 -54.98	-282.84	284.70	12.00	12.00	0.00
6,075.00	69.64	259.00	5,942.31	-59.40	-305.61	307.62	12.00	12.00	0.00
6,100.00	72.64	259.00	5,950.39	-63.92	-328.83	330.99	12.00	12.00	0.00
6,125.00	75.64	259.00	5,957.23	-68.51	-352.43	354.75	12.00	12.00	0.00
CR1									
6,128.42	76.05	259.00	5,958.06	-69.14	-355.69	358.02	12.00	12.00	0.00
6,150.00	78.64	259.00	5,962.79	-73.16	-376.36	378.83	12.00	12.00	0.00
6,175.00 6,200.00	81.64 84.64	259.00 259.00	5,967.07 5,970.06	-77.86 -82.59	-400.53 -424.89	403.16 427.69	12.00 12.00	12.00 12.00	0.00 0.00
CR1A Base		_00.00	5,57 0.00	32.00	.21.00	.27.00	12.00	12.00	0.00
6,211.98	86.08	259.00	5,971.03	-84.87	-436.61	439.48	12.00	12.00	0.00



Planning Report



Database: EDM 5000.1 Single User Db

Company: Bill Barrett Corp.

 Project:
 Duchesne Co., UT (NAD27)

 Site:
 Sec.35-T4S-R6W

 Well:
 LC Tribal 4H-35-46

 Wellbore:
 Wellbore #1

 Design:
 Design #1

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well LC Tribal 4H-35-46 WELL @ 7232.00usft WELL @ 7232.00usft True

Minimum Curvature

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
6,225.00	87.64	259.00	5,971.74	-87.35	-449.38	452.33	12.00	12.00	0.00
6,250.00	90.64	259.00	5,972.12	-92.12	-473.91	477.03	12.00	12.00	0.00
	DLS 3.00° TFO 8								
6,256.60	91.43	259.00	5,972.00	-93.38	-480.39	483.55	12.00	12.00	0.00
6,300.00	91.43	260.30	5,970.92	-101.17	-523.07	526.49	3.00	0.01	3.00
6,400.00	91.44	263.30	5,968.41	-115.42	-622.00	625.89	3.00	0.00	3.00
6,500.00	91.44	266.30	5,965.90	-124.48	-721.55	725.70	3.00	0.00	3.00
6,600.00	91.43	269.31	5,963.40	-128.31	-821.43	825.66	3.00	2.00	3.00
Start 2432.8	1 hold at 6627.50	MD							•
6,627.50	91.43	270.13	5,962.71	-128.44	-848.93	853.14	3.00	_{0.01}	3.00
6,700.00	91.43	270.13	5,960.91	-128.28	-921.40	925.56	0.00	0.00	0.00
6,800.00	91.43	270.13	5,958.41	-128.05	-1,021.37	1,025.45	0.00	0.00	0.00
6,900.00	91.43	270.13	5,955.91	-127.82	-1,121.34	1,125.34	0.00	0.00	0.00
7,000.00	91.43	270.13	5,953.42	-127.59	-1,221.31	1,225.23	0.00	0.00	0.00
7,100.00	91.43	270.13	5,950.92	-127.36	-1,321.28	1,325,12	0.00	0.00	0.00
7,200.00	91.43	270.13	5,948.43	-127.14	-1,421.25	1,425.01	0.00	0.00	0.00
7,300.00	91.43	270.13	5,945.93	-126.91	-1,521,21	1,524.90	0.00	0.00	0.00
7,400.00	91.43	270.13	5,943.44	-126.68	-1.621.18	1,624.79	0.00	0.00	0.00
7,500.00	91.43	270.13	5,940.94	126.45	-1,721.15	1,724.68	0.00	0.00	0.00
7,600.00	91.43	270.13	5,938.45	-126.23	-1,821.12	1,824.57	0.00	0.00	0.00
7,700.00	91.43	270.13	5,935.95	-126.00	-1,921.09	1,924.46	0.00	0.00	0.00
7,800.00	91.43	270.13	5,933.45	-125.77	-2,021.06	2,024.35	0.00	0.00	0.00
7,900.00	91.43	270.13	5,930,96	-125.54	-2,121.03	2,124.24	0.00	0.00	0.00
8,000.00	91.43	270 13	5,928.46	-125.31	-2,220.99	2,224.13	0.00	0.00	0.00
8,100.00	91.43	270.13	5,925.97	-125.09	-2,320.96	2,324.02	0.00	0.00	0.00
8,200.00	91.43	270.13	5,923.47	-124.86	-2,420.93	2,423.91	0.00	0.00	0.00
8,300.00	91 43	270.13	5,920.98	-124.63	-2,520.90	2,523.80	0.00	0.00	0.00
8,400.00	0148	270.13	5,918.48	-124.40	-2,620.87	2,623.69	0.00	0.00	0.00
8,500.00	91.43	270.13	5,915.99	-124.17	-2,720.84	2,723.58	0.00	0.00	0.00
8,600.00	91.43	270.13	5,913.49	-123.95	-2,820.81	2,823.47	0.00	0.00	0.00
8,700.00	91.43	270.13	5,910.99	-123.72	-2,920.77	2,923.36	0.00	0.00	0.00
8,800.00	91.43	270.13	5,908.50	-123.49	-3,020.74	3,023.25	0.00	0.00	0.00
8,900.00	91.43	270.13	5,906.00	-123.26	-3,120.71	3,123.14	0.00	0.00	0.00
9,000.00	91.43	270.13	5,903.51	-123.24	-3,220.68	3,223.03	0.00	0.00	0.00
,	2 - LCT 4H-35-46		0,000.01	0.01	5,220.00	5,225.00	0.00	0.00	0.00
9,060.32	91.43	270.13	5,902.00	-122.90	-3,280.98	3,283.28	0.00	0.00	0.00

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
LCT 4H-35-46 PBHL - plan hits target cen - Point	0.00 ter	0.00	5,902.00	-122.90	-3,280.98	643,139.002	2,269,517.755	40° 5′ 42.382 N	110° 32' 11.681 W



Design:

Sharewell Energy Services, LP

Planning Report

TVD Reference:

MD Reference:

Local Co-ordinate Reference:



EDM 5000.1 Single User Db Database:

Bill Barrett Corp.

Design #1

Company: Project: Duchesne Co., UT (NAD27) Sec.35-T4S-R6W Site: Well: LC Tribal 4H-35-46 Wellbore:

North Reference: **Survey Calculation Method:** Wellbore #1

Well LC Tribal 4H-35-46 WELL @ 7232.00usft WELL @ 7232.00usft Minimum Curvature

Formations							
	Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	2,112.00	2,112.00	Green River		-1.43	267.85	
	2,767.00	2,767.00	Mahogany		-1.43	267.85	
	3,842.00	3,842.00	Tgr3 Mkr		-1.43	267.85	
	4,627.00	4,627.00	Douglas Creek		-1.43	267.85	
	4,987.00	4,987.00	3PT Mkr.		-1.43	267.85	
	5,357.00	5,357.00	Black Shale		-1.43	267.85	
	5,597.52	5,597.00	Castle Peak		-1.43	267.85	
	6,010.32	5,922.00	Uteland Butte		-1.43	267.85	
	6,128.42	5,967.00	CR1		-1.4	267.85	
	6,211.98	5,982.00	CR1A Base		-1.43	267.85	

Plan Annotation	s					
	Measured Depth (usft)	Vertical Depth (usft)	Local Coor +N/-S (usft)	rdinates +E/-W (usft)	Comprisor O. P.	
	5,494.68 6,256.60 6,627.50 9,060.32	5,494.68 5,972.00 5,962.71 5,902.00	0.00 -93.38 -128.44 -122.90	0.00 -480.89 848.93 -3,280.98	OF / Start Build 12.00° EOC / Start DLS 3.00° TFO 89.86 Start 2432.81 hold at 6627.50 MD TD at 9060.32	
		+117	ne			
,	R					

SURFACE USE PLAN

BILL BARRETT CORPORATION <u>LC Tribal 1-35D-46 & LC Tribal 4H-35-46 Pad</u> Duchesne County, Utah

LC Tribal 1-35D-46

LC Tribal 4H-35-46

NENE, 538' FNL & 1256' FEL, Sec. 35, T4S-R6W (surface hole) NENE, 700' FNL & 700' FEL, Sec. 35, T4S-R6W (bottom hole)

NENE, 552' FNL & 1265' FEL, Sec. 35, T4S-R6W (surface hole) NWNW, 700' FNL & 700' FWL, Sec. 35, T4S-R6W (bottom hole)

The onsite inspection for this pad occurred on March 21, 2012. This is a new pad with a total of two proposed wells. Plat changes and site specific stipulations requested at the onsite are reflected within this APD and summarized below.

- a) Landowner requested red, white and blue tanks;
- b) Production equipment to be located at corner 6 to maximize interim reclamation.

The excavation contractor would be provided with an approved copy of the surface use plan of operations before initiating construction.

1. Existing Roads:

- a. The proposed well site is located approximately 17.6 miles southwest of Duchesne, Utah, take and directions reflecting the route to the proposed well site are included (see Topographic maps A and B).
- b. The existing State Highway 191 would be utilized from Duchesne for 3.5 miles of the existing BBC maintained Skitzy Road that would be utilized for 6.6 miles and provides access to the existing 7-3-56 DLB access road that would be utilized for 5.8 miles and provides access to the planned new access road.
- c. Project roads would require routine year-round maintenance to provide year-round access. Maintenance would include inspections, reduction of ruts and holes, maintenance to keep water off the road, replacement of surfacing materials, and clearing of sediment blocking ditches and culverts. Should snow removal become necessary, roads would be cleared with a motor grader and snow would be stored along the down gradient side to prohibit runoff onto the road. Aggregate would be used as necessary to maintain a solid running surface and minimize dust generation.
- d. Vehicle operators would obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions. Travel would be limited to the existing access roads and proposed access road.
- e. The use of roads under State and Duchesne County Road Department maintenance are necessary to access the project area with no improvements

proposed. A public road approach permit is not required since no new or upgraded road approach is required for this project.

f. All existing roads would be maintained and kept in good repair during all phases of operation.

2. Planned Access Road:

- a. Approximately 207 feet of new access road trending south is planned from the existing LC Tribal 15-24D-46 access road (H62-2012-129). The LC Tribal 15-24D-46 access road continues an additional 8,762 feet northeast from the existing 7-3-56 DLB access road (see Topographic Map B). The proposed access road crosses entirely private surface.
- b. The planned access road would be constructed to a 30-foot ROW width with an 18-foot travel surface. See section 12.d. below for disturbance estimates.
- c. New road construction and improvements of existing roads yould typically require the use of motor graders, crawler tractors 10-yard end dump trucks, and water trucks. The standard methodology for building new roads involves the use of a crawler tractor or track hoe to windrow the vegetation to one side of the road corridor, remove topsointo-the opposing side of the corridor, and rough-in the roadway. This is followed by a grader or bulldozer to establish barrow ditches and crown the road our face. Where culverts are required, a track hoe or backhoe would treach the road and install the culverts. Some hand labor would be required when installing and armoring culverts. Road base or gravel in some instances would be necessary and would be hauled in and a grader used to shooth the running surface.
- The proposed road would be constructed to facilitate drainage, control erosion and minimize visual impacts by following natural contours where practical. No unnecessary side-casting of material would occur on steep slopes.
- e. A maximum grade of 10% would be maintained throughout the project with minimum cuts and fills, as necessary, to access the well.
- f. Excess rock from construction of the pad may be used for surfacing of the access road if necessary. Any additional aggregate necessary would be obtained from private or State of Utah lands in conformance with applicable regulations. Aggregate would be of sufficient size, type, and amount to allow all weather access and alleviate dust.
- g. Where topsoil removal is necessary, it would be windrowed (i.e. stockpiled/accumulated along the edge of the ROW and in a low row/pile parallel with the ROW) and re-spread over the disturbed area after construction and backfilling are completed. Vegetation removed from the disturbed area would also be re-spread to provide protection, nutrient recycling, and a seed source for reclamation.

- h. Turnouts are not proposed.
- i. No culverts or low-water crossings are anticipated. Adequate drainage structures, where necessary, would be incorporated into the remainder of the road to prevent soil erosion and accommodate all-weather traffic.
- j. No cattle guards are anticipated at this time.
- k. Surface disturbance and vehicular travel would be limited to the approved location access road. Adequate signs would be posted, as necessary, to warn the public of project related traffic.
- 1. All access roads and surface disturbing activities would conform to the appropriate standard, **no higher than necessary**, to accommodate their intended function adequately as outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Cas Exploration and Development, Fourth Edition Revised 2007.
- m. The operator would be responsible for all maintenance needs of the new access road.
- 3. <u>Location of Existing Wells (see One-Mile Radius Map):</u>
 - a. Following is a list of wells with surface hole locations within a one-mile radius of the proposed pad.

i	water wells	none
	i. injection wells	none
i	ii. disposal wells	none
i	v. drilling wells	none
1	v. temp shut-in wells	none
V	vi. producing wells	none
V	vii. abandoned wells	three

4. <u>Location of Production Facilities</u>

- a. Surface facilities would consist of a wellhead, separator, gas meter, combustor, (1) 500 gal methanol tank, (1) 500 glycol tank, (3) 500 bbl oil tanks, (1) 500 bbl water tank, (1) 500 bbl test tank, (1) 1000 gal propane tank, a pumping unit or Roto-flex unit or ESP or gas lift unit, electrical or with a natural gas or diesel fired motor, solar panels, solar chemical and methanol pumps and one trace pump. See attached proposed facility diagram.
- b. Most wells would be fitted with a pump jack or Roto-flex unit or ESP or gas lift to assist liquid production. The prime mover for pump jacks or Roto-flex units would be small (100 horsepower or less), electric motor or natural gas or diesel fired internal combustion engines. If a gas lift is installed, it would be set on a

10 ft x 25 ft pad and the prime mover would be a natural gas-fired internal combustion engine rated at 200 horsepower or less or an electric compressor of similar horsepower powered by electricity.

- c. The tank battery would be surrounded by a secondary containment berm of sufficient capacity to contain 1.1 times the entire capacity of the largest single tank and sufficient freeboard to contain precipitation. All loading lines and valves would be placed inside the berm surrounding the tank battery or would utilize catchment basins to contain spills. All liquid hydrocarbon production and measurement shall conform to the provisions of 43 CFR 3162.7-2 and Onshore Oil and Gas Order No. 4 for the measurement of oil.
- d. Gas meter run(s) would be constructed and located on lease within 500 feet of the wellheads. Meter runs would be housed and/or fenced. As practicably feasible, meters would be equipped with remote telemetry monitoring systems. All gas production and measurement shall comply with the provisions of 43 CFR 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.
- e. A combustor may be installed at this location for control of associated condensate tank emissions. A combustor ranges from 24 inches to 48 inches wide and is approximately 27 ft. all. Combustor placement would be on existing disturbance.
- f. Approximately 28 I feet of pipeline corridor (see Topographic Map C) containing up to three lines (one gas pipeline up to 8 inch in diameter, one water line up to 4 inch in diameter and one residue line up to 4 inch in diameter) is proposed trending north to the existing LC Tribal 15-24D-46 pipeline corridor (H32-2012-130). The LC Tribal 15-24D-46 continues an additional 8,762 feet to the existing 7-3-56 DLB pipeline corridor. Pipelines would be constructed of steel, polyethylene or fiberglass and would connect to the proposed pipeline servicing nearby BBC wells. The pipeline crosses entirely private surface.
- g. The new segment of gas pipeline would be surface laid within a 30 foot wide pipeline corridor adjacent to the proposed access road. See 12.d below for disturbance estimates.
- h. Construction of the ROW would temporarily utilize the 30 foot disturbed width for the road for a total disturbed width of 60 foot for the road and pipeline corridors. The use of the proposed well site and access roads would facilitate the staging of the pipeline construction.
- Pipeline construction methods and practices would be planned and conducted by BBC with the objective of enhancing reclamation and fostering the reestablishment of the native plant community.
- j. All permanent above-ground structures would be painted according to the surface owner's recommendation. All facilities would be painted the designated

color at the time of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.

- k. Site security guidelines identified in 43 CFR 3162.7-5 and Onshore Oil and Gas Order No. 3 would be adhered to. Any modifications to proposed facilities would be reflected in the site security diagram submitted.
- 1. The site would require periodic maintenance to ensure that drainages are kept open and free of debris, and that surfaces are properly treated to reduce erosion, fugitive dust, and impacts to adjacent areas.
- 5. <u>Location and Type of Water Supply:</u>

a. Water for the drilling and completion would be trucked from any of the following locations:

Water Right No. and Application or Change No.	Applicant	Allocation	Date	Point of Diversion	Source
43-180	Duchesne City Water Service District	5 cfs	(13) 2004	Knight Diversion Dam	Duchesne River
43-1202, Change a13837	Myton City	5.49.efr and 3967 acre feet	3/21/1986	Knight Diversion Dam	Duchesne River
43-10444, Appln A57477	I uchesne County Upper Country Water	2 cfs	1994	Ditch at Source	Cow Canyon Spring
43-10446, Apply 1-574-2	Duchesne County Upper Country Water	1.58 cfs	1994	Ditch at Source	Cow Canyon Spring
8-12/3, Appln A17462	J.J.N.P. Company	7 cfs	1946	Strawberry River	Strawberry River
43-1273, Appln t36590	J.J.N.P. Company	4 cfs	6/03/2010	Strawberry River	Strawberry River
43-2505, Appln t37379	McKinnon Ranch Properties, LC	1.3 cfs	4/28/2011	Pumped from Sec, 17, T4SR6W	Water Canyon Lake
43-12415, Change A17215a	Peatross Ranch, LLC	1.89 cfs	09/2011	Dugout Pond	Strawberry River

- b. No new water well is proposed with this application.
- c. Should additional water sources be pursued they would be properly permitted through the State of Utah Division of Water Rights.

d. Water use would vary in accordance with the formations to be drilled but would be up to approximately 5.41 acre feet for drilling and completion operations.

6. Source of Construction Material:

- a. The use of materials would conform to 43 CFR 3610.2-3.
- b. No construction materials would be removed from the lease or EDA area.
- c. If any additional gravel is required, it would be obtained from a local supplier having a permitted source of materials within the general area.

7. <u>Methods of Handling Waste Disposal:</u>

- a. All wastes associated with this application would be contained and disposed of utilizing approved facilities.
- b. The reserve pit would be constructed so as not to leak break or allow any discharge.
- c. The reserve would be lined with 12 mil and intum thickness polyethylene nylon reinforced liner material. The liner () would overlay straw, dirt and/or bentonite if rock is encountered during excapation. The liner would overlap the pit walls and be covered with dirt and/or rocks to hold them in place. No trash, scrap pipe, or other materials that could puncture the liner would be discarded in the pit. A minimum of two feet of free board would be maintained between the maximum fletid level and the top of the reserve pit at all times.
 - To deter livestock from entering the pit, the three sides exterior to the location would be fenced before drilling starts. Following the conclusion of drilling and completion activities, the fourth side would also be fenced.
- e. Drill cuttings would be contained in the pit and buried on-site for a period not to exceed six months, weather permitting
- f. Produced fluids from the well other than water would be decanted into steel test tank(s) until such time as construction of production facilities is completed. Any oil that may be accumulated would be transferred to a permanent production tank. Produced water may be used in further drilling and completion activities, evaporated in the pit, or would be hauled to one of the following state-approved disposal facilities:

Disposal Facilities

- 1. RNI Industries, Inc. Pleasant Valley Disposal Pits, Sec. 25, 26, 35 & 36, T4S-R3W
- 2. Pro Water LLC Blue Bench 13-1 Disposal Well (43-013-30971) NENE, Sec. 13, T3S-R5W

Disposal Facilities

- 3. RN Industries, Inc. Bluebell Disposal Ponds, Sec. 2, 4 & 9, T2S-R2W
- 4. Water Disposal, Inc. Harmston 1-32-A1 Disposal Well (43-013-30224), UTR #00707, Sec. 32, T1S-R1W
- 5. Unified Water Pits Sec. 31, T2S-R4W
- 6. Iowa Tank Line Pits 8500 BLM Fence Road, Pleasant Valley
- 7. Western Water Solutions Sand Pass Ranch, Sections 9 and 10, T4S-R1W, permit #WD-01-2011
- g. Any salts and/or chemicals, which are an integral part of the drilling system, would be disposed of in the same manner as the drilling fluid.
- h. Any spills of oil, condensate, produced or frac water, drilling fluids, or other potentially deleterious substances would be recovered and either returned to its origin or disposed of at an approved disposal site, most likely in Duchesne, Utah.
- i. Chemicals on the EPA's Consolidated List of Chemicals subject to reporting under Title III of the Superfund Amendments and reauthorization Act of 1986 (SARA) may be used or stored in quantities a terreportable quantities. In the course of drilling, BBC could potentially store and use diesel fuel, sand (silica), hydrochloric acid, and CO₂ gas, all less med as hazardous substances in 40 CFR Part 302, Section 302.4, in quantities exceeding 10,000 pounds. In addition, natural gas condensate and crude oil and methanol may be stored or used in reportable quantities. Small quantities of retail products (paint/spray paints, solvents { cg., WD-40}, and lubrication oil) containing non-reportable volumes of hazardous substances may be stored and used on site at any time. No extremely hazardous substances, as defined in 40 CFR 355, would be used, produced, stored, transported or disposed of in association with the drilling, testing or completion of the wells.
- j. Portable toilets and trash containers would be located onsite during drilling and completion operations. A commercial supplier would install and maintain portable toilets and equipment and would be responsible for removing sanitary waste. Sanitary waste facilities (i.e. toilet holding tanks) would be regularly pumped and their contents disposed of at approved sewage disposal facilities in Duchesne, and/or Uintah Counties, in accordance with applicable rules and regulations regarding sewage treatment and disposal. Accumulated trash and nonflammable waste materials would be hauled to an approved landfill once a week or as often as necessary. All debris and waste materials not contained in the trash containers would be cleaned up, removed from the construction ROW, well pad, or worker housing location, and disposed of at an approved landfill. Trash would be cleaned up everyday.
- k. Sanitary waste equipment and trash bins would be removed from the Project Area upon completion of access road or pipeline construction; following drilling and completion operations at an individual well pad; when worker housing is no longer needed; or as required.

- 1. A flare pit may be constructed a minimum of 110' from the wellhead(s) and may be used during completion work. In the event a flare pit proves to be unworkable, a temporary flare stack or open top tank would be installed. BBC would flow back as much fluid and gas as possible into pressurized vessels, separating the fluids from the gas. In some instances, due to the completion fluids utilized within the Project Area, it is not feasible to direct the flow stream from the wellbore through pressurized vessels. In such instances BBC proposes to direct the flow to the open top tanks until flow through the pressurized vessels is feasible. At which point the fluid would either be returned to the reserve pit or placed into a tank(s). The gas would be directed to the flare pit, flare stack (each with a constant source of ignition), or may be directed into the sales pipeline.
- m. Hydrocarbons would be removed from the reserve pit would as soon as practical. In the event immediate removal is not practical, the reserve pit would be flagged overhead or covered with wire or plastic mesh to protect migrating birds.

8. <u>Ancillary Facilities:</u>

- a. Garbage containers and portable toilets would be located on the well pad.
- b. On well pads where active drilling and completion is occurring, temporary housing would be provided on location for the well pad supervisor, geologist, tool pusher, and others that are required to be on location at all times. The well pad could include up to five single wide mobile homes or fifth wheel campers/trailers.
- c. A surface powerline corridor is not proposed at this time but may be proposed in he future when infrastructure becomes available.

Well Site Layout:

- a. The well would be properly identified in accordance with 43 CFR 3162.6.
- b. The pad layout, cross section diagrams and rig layout are enclosed (see Figures 1 and 2).
- c. The pad and road designs are consistent with industry specifications.
- d. The pad has been staked at its maximum size of 384 feet x 305 feet with an inboard reserve pit size of 210 feet x 100 feet x 8 feet deep. See section 12.d below for disturbance estimates.
- e. Within the approved well pad location, a crawler tractor would strip whatever topsoil is present and stockpile it along the edge of the well pad for use during reclamation. Vegetation would be distributed along the sides of the well pad.

- f. Fill from pit excavation would be stockpiled along the edge of the pit and the adjacent edge of the well pad.
- g. Use of erosion control measures, including proper grading to minimize slopes, diversion terraces and ditches, mulching, terracing, riprap, fiber matting, temporary sediment traps, and broad-based drainage dips or low water crossings would be employed by BBC as necessary and appropriate to minimize erosion and surface runoff during well pad construction and operation. Cut and fill slopes would be constructed such that stability would be maintained for the life of the activity.
- h. All cut and fill slopes would be such that stability can be maintained for the life of the activity.
- i. Diversion ditches would be constructed, if necessary, around the well site prevent surface waters from entering the well site area.
- j. Water application may be implemented if necessary to minimize the amount of fugitive dust.
- k. All surface disturbing activities would be supervised by a qualified, responsible company representative who is a vare of the terms and conditions of the APD and specifications in the approved plans.

10. Plan for Restoration of the Surface:

- a. A site specific reclamation plan would be submitted, if requested, within 90 days of location construction to the surface managing agency.
- b. Site reclamation would be accomplished for portions of the well pad not required for the continued operation of the well on this pad within six months of completion, weather permitting.
- c. The operator would control noxious weeds along access road use authorizations and well site by spraying or mechanical removal, according to the Utah Noxious Weed Act and as set forth in the approved surface damage agreements.
- d. Rat and mouse holes would be filled and compacted from bottom to top immediately upon release of the drilling rig from location. Upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1. The reserve pit would be allowed to dry prior to the commencement of backfilling work. No attempts would be made to backfill the reserve pit until it is free of standing water. Once dry, the liner would be torn and perforated before backfilling.
- e. The reserve pit and that portion of the location not needed for production facilities/operations would be recontoured to the approximate natural contours. Areas not used for production purposes would be backfilled and blended into the

surrounding terrain, reseeded and erosion control measures installed. Mulching, erosion control measures and fertilization may be required to achieve acceptable stabilization. Back slopes and fore slopes would be reduced as practical and scarified with the contour. The reserved topsoil would be evenly distributed over the slopes and scarified along the contour. Slopes would be seeded with the landowner specified seed mix.

f. Topsoil salvaged from the drill site and stored for more than one year would be placed at the location indicated on the well site layout drawing and graded to a depth optimum to maintain topsoil viability, seeded with the landowner prescribed seed mixture and covered with mulch for protection from wind and water erosion and to discourage the invasion of weeds.

11. Surface and Mineral Ownership:

- a. Surface ownership Bill Barrett Corporation
- b. Mineral ownership Ute Indian Tribe 988 South 7500 Fast Ft. Duchesne, Utah 84026; 435-725-4982.

12. Other Information:

- a. Montgomery Archeological Constitants has conducted a Class III archeological survey. A copy of the report has been submitted under separate cover to the appropriate agencies by Montgomery as report 12-020 dated March 20, 2012.
 - . BBC would require that their personnel, contractors, and subcontractors to edmily with Federal regulations intended to protect archeological and cultural resources.
- c. Project personnel and contractors would be educated on and subject to the following requirements:
 - No dogs or firearms within the Project Area.
 - No littering within the Project Area.
 - Smoking within the Project Area would only be allowed in off-operator active locations or in specifically designated smoking areas. All cigarette butts would be placed in appropriate containers and not thrown on the ground or out windows of vehicles; personnel and contractors would abide by all fire restriction orders.
 - Campfires or uncontained fires of any kind would be prohibited.
 - Portable generators used in the Project Area would have spark arrestors.

d. Disturbance estimates:

Approximate Acreage Disturbances

Well Pad		3.667	acres
Access	207 feet	0.125	acres
Pipeline	281 feet	0.175	acres

Total 3.967 acres



OPERATOR CERTIFICATION

Certification:

I hereby certify that I, or someone under my direction supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein would be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application and that bond coverage is provided under Bill Barrett Corporations federal nationwide bond. These statements are subject to the provisions of 18 U.S.C. 1001 for the filings of false statements.

Executed this

day of

2012

Name:

enessa Langmacher

Position Title:

Senior Permit Analyst

Address:

1099 18th Street, Suite 2300, Dem en C 30202

Telephone:

303-312-8172

E-mail:

vlangmacher@billharreftcorp.com

Field Representative

Kary Eldredge Bill Barren Corporation

Address:

820 W. Highway 40, Roosevelt, UT 84066

Telephone:

435,721,331,5 (office); 435-724-6789 (mobile)


E-mail:

el redge@billbarrettcorp.com

enessa Langmacher, Senior Permit Analyst


BILL BARRETT CORPORATION

TYPICAL 5,000 p.s.i. BLOWOUT PREVENTER



BILL BARRETT CORPORATION

TYPICAL 5,000 p.s.i. CHOKE MANIFOLD





May 29, 2012

Ms. Diana Mason, Petroleum Technician State of Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210 P. O. Box 145801 Salt Lake City, Utah 84114-5801

RE: Horizontal Drilling

LC Tribal # 4H-35-46

Section 35, T4S-R6W, U.S.B.&M.

Duchesne County, Utah

Surface Hole Location: 552' FNL & 1265' FEL, NENE, 35-T4S-R6W, USB&M Bottom Hole Location: 700' FNL & 700' FWL, NWNW, 35-T4S-R6W, USB&M

Dear Ms. Mason:

Pursuant to the filing of Bill Barrett Corporation's ("BBC") Application for Permit to Drill ("APD") regarding the above-referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Order 139-87 pertaining to a 640 acre spacing unit for a horizontal or vertical well.

- Tribal Exploration and Development Agreement #14-20-H62-5500, which includes all
 of the subject Section 35 and other lands, allows for the drilling of the #4H-35-46 well.
- Once the well has been drifted and completed BBC will earn the tribal lease covering 640 "deep depth acres being further described in the Exploration and Development Agreement."

The Last Hamiltonian Tribal #4H-35-46 will be perforated no less than 660 feet from the Section 35 Thibal Lease boundary, in accordance with UDOGM Order #139-87.


Based on the information provided, BBC requests that the permit be granted pursuant to Order #139-87. If you should have any questions or need further information, please contact me at 303-312-8544.


Sincerely,


BILL BARRETT CORPORATION


David Watts Landman


> 1099 18TH STREET SUITE 2300 DENVER, CO 80202 P 303.293.9100 F 303.291.0420











State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

May 30, 2012

BILL BARRETT CORP 1099 18th Street Ste 2300 Denver, CO 80202

Re: Application for Permit to Drill - UINTAH County, Utah

Ladies and Gentlemen:

The Application for Permit to Drill (APD) for the LC Tribal 4H-35-46 well, API 43047527690000 that was submitted May 29, 2012 is being returned unapproved. If you plan on drilling this well in the future, you must first submit a new application.

Should you have any questions regarding this matter, please call me at (801) 538-5312.

Sincerely,

Diana Mason Environmental Scientist

Enclosure

cc: Bureau of Land Management, Vernal, Utah

